


THE Upper Air Opening Slide


It was used back in the 1930s and '40s to reduce the spread of measles in...

NIOSH established guidelines for controlling Tuberculosis...

Upper room GUV is the most tried, tested, and proven method for air disinfection...



**Environmental Control for Tuberculosis:
Basic Upper-Room Ultraviolet
Germicidal Irradiation Guidelines
for Healthcare Settings**



Department of Health and Human Services
Centers for Disease Control and Prevention
National Institute for Occupational Safety and Health



Our Expectations of the “General” Marketplace

Confidential



Lack of Awareness

Largely Unadopted
Technology



Lack of Resilience

Resistance to
Complexity & Calculation



Lack of Trust

Poor Communication of
Solution Effectiveness

Our Expectations of the “General” Marketplace

Confidential



Lack of Awareness

Largely Unadopted
Technology

**Raise
Awareness**



Lack of Resilience

Resistance to
Complexity & Calculation

**Simplify
Solutions**




Lack of Trust

Poor Communication of
Solution Effectiveness

**Share
Benefits**

WHAT DID WE DO?



We Followed the Flow Chart

Streamline Guidance – Commissioning Flowchart


The proposed commissioning design flowchart (see Figure 1, Draft November 2022) maps the entire commissioning process from needs assessment to implementation to build the project brief.

The Commissioning process is embedded in the GPC 37 Guideline (ANSI/ASHRAE/IES 202 and 90.1) which states,

“commissioning is a quality-focused process for enhancing the delivery of a project”

that focuses upon verifying and documenting that a project is

“planned, designed, installed, tested, operated and maintained to meet Requirements.”




Following the Flow Chart

Confidential

We used the Commissioning Steps outlined in five project phases:

- 1) Pre-Design
- 2) Design
- 3) Construction/Installation
- 4) Acceptance/Operations
- 5) Post-Installation



Confidential

PRE-DESIGN



Austin, TX

www.lhc.org

About Lake Hills Church Facilities

A community of 2,500 people of all ages and an average weekly attendance of 1,200 people.

Main Office ~2,000 ft² for administrative use.


Warehouse ~3,000 ft² for storage and ministry operations

Student Building ~2,000 ft² used for youth ages 13-18

Kids Building ~19,000 ft² dedicated to children ages 3-12 with individual class rooms and large gathering areas.

Worship Center ~ 18,000 ft² with 1,200 seats, nurseries for kids age 0-2, as well as stage and production space.





We analyzed the building environments with their pastor and facility manager to evaluate the following factors:

Purpose, Size, Ventilation, Ceiling Construction, Layout, Furniture and Fixtures, Existing electrical appliances.

All the buildings have modern HVAC with contingencies for drastically increasing airflow in times of dense occupation.

The HVAC is well maintained and managed giving confidence that a meaningful amount of air mixing is occurring as a matter of standard practice.

About Lake Hills Church Facilities

A community of 2,500 people of all ages and an average weekly attendance of 1,200 people.

Main Office ~2,000 ft² for administrative use.

Warehouse ~3,000 ft² for storage and ministry operations

Student Building ~2,000 ft² used for youth ages 13-18

Kids Building ~19,000 ft² dedicated to children ages 3-12 with individual class rooms and large gathering areas.

Worship Center ~ 18,000 ft² with 1,200 seats, nurseries for kids age 0-2, as well as stage and production space.




Risk Assessment & Room Selection

Ruling out large environments that were not regularly populated or had plenty of fresh air ventilation, we identified 5 potential areas for application in the Kids Building and Worship Center based on room usage, characteristics and primary occupants:


- 1: Adult Worship Center
- 2: 3 Nurseries
- 3: Club K12 Room
- 4: 345 Room
- 5: Kids Worship

The budget priority reduced us to 3 areas mitigating risk for the oldest and youngest in the community:

- 1: Adult Worship Center
- 2: 3 Nurseries
- 3: Club K12 Room



Area 1: Worship Center



Confidential

Risk Characteristics

Duration of Occupancy	1 day a week / 3 hours a week
Density of Room Occupants	1,200 seat capacity
Activity type	Sunday Service (Singing / Talking)
Epidemiological characteristics	General Population

Space Characteristics

Sizes (+ ceiling heights)	115' x 50' x Height from 11' to 30'
Volume	~185,000 Cubic Feet
Shape	Sector
Windows and Doors	No windows, 2 doors
Any Obstructions	Lighthing fixtures, various audio appliances hanging


Airflow Patterns Evaluation

Ventilation System	Air Conditioning
Location of Diffusers	(see illustration)
Potential Air Current	8-17 ACH

Lake Hills Church Evaluation


Confidential

Area 1: Worship Center




① = Location of the directors of the ceiling steel structure over which the power runs and where the lights are placed.




Air Vents



Ceiling Heights



Area 2: Nursery (3 identical rooms)



Risk Characteristics

Duration of Occupancy	1 day a week / 5 hours a week
Density of Room Occupants	10 people (2 adults, 8 children)
Activity type	Caring and playing, breast feeding, diaper changing.
Epidemiological characteristics	Newborn to 2-year old children

Space Characteristics

Sizes (+ ceiling heights)	14.9' ÷ 16.8' x 16.8' x 9.7' Height
Volume	~2,500 Cubic Feet
Shape	Rectangular
Windows and Doors	No opening windows, 1 door
Any Obstructions	No, counter ceiling.

Airflow Patterns Evaluation

Ventilation System	AC
Location of Diffusers	(see draw)
Potential Air Current	8-17 ACH

Area 3: K12 Room



Confidential

Risk Characteristics

Duration of Occupancy	1 day a week / 3 hours a week
Density of Room Occupants	Full capacity 100 people
Activity type	Singing / Talking / Play Activities)
Epidemiological characteristics	Children




Space Characteristics

Sizes (+ ceiling heights)	49' x 45' x 12.6' Height
Volume	~27,800 Cubic Feet
Shape	Square
Windows and Doors	No windows, 2 doors
Any Obstructions	Lighthing fixtures, various audio appliances hanging

Airflow Patterns Evaluation


Ventilation System	Air Conditioning
Location of Diffusers	(see draw)
Potential Air Current	8-17 ACH

APPLICATION DESIGN



Application Design

Confidential





Application Design

Confidential

Area 1: Worship Center

13 Devices (UV-FLOW 4/18P-CL)




Confidential

Area 3: K12 room


Option 1: 2 Devices (UV-FLOW 4/18P-CL)

Option 2: 4 Devices (UV-FLOW 16-WL)

Option 1



Option 2




Application Design

Area 3: K12 room

Option 1: 2 Devices (UV-FLOW 4/18P-CL)

~~Option 2: 4 Devices (UV-FLOW 16-WL)~~

Option 1




Application Design


Confidential

Area 2: Nursery (3 identical rooms)

1 Device (UV-FLOW 8-WL)








Confidential



Application Design

Beyond producing CAD Drawings, we modelled/calculated dosage and product performance using goniophotometry (i.e., IES files) to select the products and placement.




Area 1: Worship Center

Too visually disruptive when people are inside the dark.

Ceiling is not easily accessible for maintenance.

Alternative viable solution to add GUV to the HVAC system serving the Worship Center



Application Design

Final Area Selection:

~~1: Adult Worship Center~~

2: 3 Nurseries

3: Club K12 Room




Learnings:

From Design to Installation there is also consideration for a variety of customer-centric issues:


Usability and Maintenance.

Integration with other behaviors, practices, or protocols.

Aesthetic considerations.



INSTALLATION



Learnings:


Teach the building to GUV Experts
OR teach GUV to the building
experts.

Installer training on safety &
intended use of the devices. Read
the manual!


Share precise installation
instructions.

Provide project intent, design
constraints, and exact desired
positioning.

Hope you don't discover physical
realities change the economics.



ACCEPTANCE & TESTING



Clearly documented testing methodologies:

Anghiari, 29/06/2023

GUIDELINE FOR SAFE MEASUREMENT AND COMMISSIONING OF UPPER-ROOM GUV DEVICES

Check List and methods for verifying proper compliance with design parameters of installation direct light devices.

1. EQUIPMENT AND MATERIAL REQUIRED FOR THE MEASUREMENT

Ckt	Op.	Activity Description	Notes
01	PPE	Protective helmet equipped with a facemask Long-sleeved shirt Closed shoes Long pants Protection Gloves	
02	Measuring instruments and accessories	UVC measuring instrument with suitable probe Adjustable measuring stand to place the UVC probe at 2.1 mt. (7 feet) height Field of View (FOV) Cone 80° to be fixed on the probe	We recommend GIOHARTZ X1.5 - probe UV-3726-5
03	Miscellaneous Accessories	Tape measure min. length 2.5 Mt. (8.2 feet) Pencil with eraser	
04	Projects	Floor plans of the room with the location of the installed devices (position and height)	

Ckt	Op.	Activity Description	Notes
01		Check that the environment corresponds with the project design drawings.	
02		Check that the wall-mounted units are installed at the right height as mentioned in the project design.	
03		Be sure devices have been operating for at least 100 h before measurement	It is needed to have a stable UV source.
03bis		Turn on the UV-C device and wait 20 minutes before performing the measurement.	It is needed to have a stable value.
04		All windows and doors shall be closed during measurements.	Sunlight can significantly alter the measurement.
05		Check for the presence of other people in the environment who are not adequately protected.	
06		Clean the sensor lens if the sensor lens is found to have dust or other substances.	
07		Fix the FOV cone to the probe and secure the probe in the measuring stand.	
08		Fix the UVC probe on the measuring stand at 2.1 m.	
09		Turn on the UVC measuring instrument and set it to measure "Hg lamps at 254 nm."	

Technical Report

SEDE LEGALE/PRODUZIONE 1: Loc. San Lorenzo, 40 - 52031 Anghiari - AR - ITALY | PRODUZIONE 2: Loc. S. Antonio, 40 - 52043 Castelginone - AR - ITALY
 (+39) 0575.746.255 - Fax (+39) 0575.789.829 | www.lightprogress.it | info@lightprogress.it | C.F. n° P. IVA 0120895017

3. CARRYING OUT THE MEASUREMENT

Op.	Activity Description	Notes
01	With the probe positioned at the height of 2.1 mt. (7 feet) move around the entire surface of the room with the probe oriented in the direction of the UV-C devices, and search for the maximum detectable intensity (see Fig. 8.1). Verify that irradiance values at all measured points are less than 0.2 uW/cm². In case you have points with higher values, note them in the plan.	
02	With the probe positioned at the height of 2.1 mt. (7 feet) move around the entire surface of the room with the probe oriented in the direction the ceiling and side walls, and search for the maximum detectable intensity. Verify that irradiance values at all measured points are less than 0.2 uW/cm². In case you have points with higher values, note them in the plan.	

Figure 8.1
Equipment Mounting Relative to Test Plane

Two dimensional test plane parallel to floor
2.1m (7 ft) above the floor
GUV = General Use Distance
FLOOR

Technical Report

SEDE LEGALE/PRODUZIONE 1: Loc. San Lorenzo, 40 - 52031 Anghiari - AR - ITALY | PRODUZIONE 2: Loc. S. Antonio, 40 - 52043 Castelginone - AR - ITALY
 (+39) 0575.746.255 - Fax (+39) 0575.789.829 | www.lightprogress.it | info@lightprogress.it | C.F. n° P. IVA 0120895017

Performance Testing

Confidential

Components of Testing:

- Room Mapping
- Sensor Selection
- UL Standards

Photobiological safety testing is done as part of the UL1598 certification and in compliance with UL 8802 (proposed) test standard. It verifies an installation height and angle at which the luminaire falls into various risk groups.




To ensure that UVC sources used in UR UV-C₂₅₄ luminaires do not generate ozone, all UR UV-C₂₅₄ designs shall be tested in compliance with UL standard UL 2998 to show zero ozone generation.



Confidential

Performance Testing

Intended disinfection is being delivered:




Performance Testing

Safety:


Grid of measured values at 7 feet from the ground.

Accepted **Threshold Limit Value** established by ACGIH is 6,000 microjoules per 8 hours for eye exposure and 10,000 microjoules per 8 hours for skin exposure.

Eye Exposure Limit Maths = **.2 microwatt/cm²**




POST-INSTALLATION



APPENDIX A — FIELD PROBLEMS NOTED IN SOME UVGI SYSTEMS

The CDC/NIOSH Health Hazard Evaluation (HHE) and Technical Assistance Program receives about 400 requests a year to conduct field investigations of potential health hazards. These requests are made by employers, workers, worker representatives, other Federal agencies, and State, foreign, and local agencies. From 1987 through 2000, the program received 14 TB-related requests for technical assistance that involved evaluations of UVGI systems [Boudreau et al. 1995; Buchta et al. 1993; Burton 1995; Burton and Martinez 1997; Decker 1993; Martinez 1995a, 1995b, 1999; Moss and Seitz 1990, 1991; Murray 1987; Seitz 1992; Seitz et al. 2000; Tubbs and Bresler 1992; Weber and Boudreau 2000]. These requests came from a variety of workplaces including hospitals (e.g., emergency rooms, waiting areas, and microbiology laboratories), neighborhood health centers, TB clinics, drug treatment centers, correctional facilities, a medical examiner's office, and a homeless shelter. A review of these requests for assistance indicates the following installation or maintenance problems were noted in at least one of the facilities during the investigations:

- Lack of preventive maintenance plans, resulting in numerous reports of dirty and/or old lamps that produced minimal UVGI levels.
- No wall switches to turn off UVGI lamps or fixtures during maintenance operations.
- UV fixture louvers bent or missing, allowing workers to look directly at the lamps.
- No warning labels on UVGI lamps or fixtures to warn of hazards from direct eye contact.
- No worker training on the potential hazards of UVGI.
- No lockout mechanisms or automatic shut-off mechanisms to rooms where the upper-room UVGI system was designed to be deactivated when people were present in the rooms.
- Polished metal and reflective paint surfaces that indirectly increased the UVGI level in the occupied space.
- No warning signs in areas with high UVGI levels.
- Improper planning and installation of fixtures.



Operation, Maintenance, and Training:


Dedicated Light Switches

Device and Light Switch Labels


Clear Safety Labels and Instructions

User Education

Maintenance Plan for Effective
Operation and Identification of
Intended Performance



CONCLUSION & REFLECTIONS



This is a helpful execution document but practice highlights the opportunity for further guidance that support's the customer's decision making process.

Who else will say, ***"When 'X', you should install Upper Air GUV to 'Y', for all of the 'Z' benefits."***

The decision making process is not as linear as we might like it to be.

There is opportunity to encourage the alignment and cooperation of stakeholders in the process: manufacturer, re-seller, installer, buyer, users, etc.

**THE PACIFIC
NORTHWEST
NATIONAL
LABORATORY
STUDY ON UPPER
AIR GUV FOR THE
U.S. DEPARTMENT
OF ENERGY**



Pacific Northwest
NATIONAL LABORATORY



U.S. DEPARTMENT OF
ENERGY





Thank you.

info@lightprogress.it



Light Progress Group SRL
Loc. San Lorenzo, 40
52031 Anghiari (AR)
ITALIA

P: (+39) 0575 749255
E: info@lightprogress.it
W: www.lightprogress.it



Light Progress GmbH
Glattbacher Str. 5
63741 Aschaffenburg
DEUTSCHLAND

P: (+49) 6021-8663700
E: info@lightprogress.it
W: www.lightprogress.de



Light Progress LLC
1601 Susan Drive,
Austin, TX 78734
USA

P: (+1) 512-649-0055
E: americas@lightprogress.it
W: www.lightprogress.us